

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-21788-00-00
Spot: NENESWSE Sec/Twnshp/Rge: 13-35S-6E
1137 feet from S Section Line, 1612 feet from E Section Line
Lease Name: HANAHAN Well #: 1
County: COWLEY Total Vertical Depth: 2916 feet

Operator License No.: 4555
Op Name: ROADRUNNER ENERGY, INC.
Address: 7225 S 85 E AVE # 100
TULSA, OK 74133

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	2710		
PROD	5.5	2916		175 SX
SURF	8.625	150		100 SXS CMT
SURF	8.625	155		87 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/19/2013 8:00 AM
Plug Co. License No.: 31539 Plug Co. Name: SAMS WELL SERVICE, INC.
Proposal Revd. from: DENNIS CLAY Company: ROADRUNNER ENERGY Phone: (918) 250-8589

Proposed Plugging Method: AS PER KCC RULES & REGS /CIBP @ 2300 W/5 SXS, 35 SXS @ 1180/ CIRC 350-0

Plugging Proposal Received By: DUANE KRUEGER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/20/2013 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE, SET CIBP @ 2320', DUMP BAILED 2 SXS CEMENT ON TOP OF PLUG. 6-20-2013, RIH W/TBG @ 1188', CONSOLIDATED MIXED & PUMPED 35 SXS CLASS A COMMON 3% CC & DISPLACED IN CASING. WAITED 2 HOURS, TAGGED CEMENT @ 1140'. TESTED CASING, HELD OK. RIH ON WIRELINE SHOT SQUEEZE HOLES @ 350'-351' (4 HOLES). SWEDGED INTO 5 1/2" CASING, CONSOLIDATED MIXED & PUMPED 175 SXS CLASS A COMMON 2% CC TO SURFACE. CEMENT CIRCULATED. CONSOLIDATED CEMENT TICKET #5000000625.

Perfs:

Top	Bot	Thru	Comments
2882	2892	CSG	
2356	2362	CSG	

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 16 2013

Remarks: COMPLIANCE 10 YR RULE

CONSERVATION DIVISION
WICHITA, KS

Plugged through: TBG

District: 02

Signed DUANE KRUEGER
8/29/13 (TECHNICIAN)

JK