

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-23170-00-00
Spot: SWNWNESE Sec/Twnshp/Rge: 17-35S-7E
2172 feet from S Section Line, 1081 feet from E Section Line
Lease Name: LARRY OLSEN (DOROTHY) Well #: 8
County: COWLEY Total Vertical Depth: 3010 feet

Operator License No.: 4555
Op Name: ROADRUNNER ENERGY, INC.
Address: 7225 S 85 E AVE # 100
TULSA, OK 74133

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1970		
CIBP	5.5	2050		
CIBP	5.5	2410		
CIBP		2770		
PROD	5.5	3028		415 SX
RBP		1970		
RBP		2050		
SURF	8.625	312		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/20/2013 8:00 AM
Plug Co. License No.: 31539 Plug Co. Name: SAMS WELL SERVICE, INC.
Proposal Rcvd. from: DENNIS CLAY Company: ROADRUNNER ENERGY Phone: (918) 250-8589

Proposed Plugging Method: Set CIBP above Lower Layton Perfs @ 2160-2175 for bottom plug. We will not pull any casing. The Perfs 1988-1998, 1954-1956 were cement squeezed. Perfs 2160-2175 were opened and produced. When the well became uneconomic a CIBP was set at 2169 and the zone from 2160-2169 was tested uneconomic. The top plug will be set as prescribed by the KCC.

Plugging Proposal Received By: JEFF KLOCK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/20/2013 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE, SET CIBP @ 1925', DUMP BAILED 2 SXS CEMENT ON TOP OF PLUG. TESTED CASING, HELD OK. RIH ON WIRELINE SHOT SQUEEZE HOLES @ 365'-366' (4 HOLES). SWEDGED INTO 5 1/2" CASING, CONSOLIDATED MIXED & PUMPED 100 SXS CLASS A COMMON TO SURFACE. CEMENT CIRCULATED. CONSOLIDATED CEMENT TICKET #5000000624.

Perfs:

Top	Bot	Thru	Comments
2962	2976	CSG	
2658	2665	CSG	
2502	2506	CSG	
2170	2190	CSG	
2160	2175	CSG	
1988	1998	CSG	
1954	1956	CSG	

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 22 2013
CONSERVATION DIVISION
WICHITA, KS

Remarks: COMPLIANCE 10 YR RULE CIBP @ 1970' / PERFS @ 2962-2976 WERE SQUEEZED W/CEMENT

Plugged through: TBG

District: 02

Signed

Duane Krueger
8/23/13
(TECHNICIAN)