

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-20284-00-02
Spot: SWNESWNW Sec/Twnshp/Rge: 24-27S-5W
3545 feet from S Section Line, 4394 feet from E Section Line
Lease Name: STANNARD Well #: 2-24
County: KINGMAN Total Vertical Depth: 4670 feet

Operator License No.: 5214
Op Name: LARIO OIL & GAS COMPANY
Address: 301 S MARKET ST
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PKR		4306		PACKER TYPE AND SETTING DEPTH: BAKER MODEL D PACKER SET @ 4306. PARALLEL ANCHOR @ 3718. 2 1/16" PRODUCTION TUBING SET @ 3718.
PROD	5.5	4328		200 SX
SURF	8.625	230		185 SX
T1	2.065	4306		

Well Type: SWD UIC Docket No: D28403.0 Date/Time to Plug: 08/14/2013 4:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 08/14/2013 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 3620' - CAPPED WITH 5 SX CEMENT ON TOP. CUT CASING PIPE OFF @ 2680' PULLED CASING TO 900' SPOTTED 35 SX CEMENT. PULLED CASING TO 470' SPOTTED 35 SX CEMENT. PULLED CASING TO 260' CIRCUALTED TO SURFACE WITH 170 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
3733	3743		

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 23 2013
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY WELL SERVICE PROVIDED CEMENT FOR WELL PLUGGING.

Plugged through: CSG

District: 02

8/29/13 Signed BJ Hope
cc to UIC 8/29/13