

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-20244-00-00  
Spot: NWSWSE Sec/Twnshp/Rge: 12-10S-24W  
990 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: GANO SE UNIT Well #: 3-1  
County: GRAHAM Total Vertical Depth: 4245 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4243		200 SX
SURF	8.625	197		175 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/12/2013 9:30 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Shot perforations at 2450', 2080', 1240' and 195'.  
Plugging Perforations at 3784' - 3790', 3798' - 3802', 3829' - 3834', 3841' - 3844', 3878' - 3880', 3939' - 3934', 3951' - 3956', 3971' -  
Method: 3974' and 3992' - 3996'.  
Ordered 500 sx 60/40 pozmix 4% gel cement w/800 # hulls.  
Tubing broken off at 3787'. Rods and pump are out of the hole.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/12/2013 1:15 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3741' and pumped 125 sx cement w/200 # hulls.  
Pulled tubing to 3182' and pumped 255 sx cement w/400 # hulls.  
Pulled tubing to 2067' and pumped 100 sx cement. Good circulation of cement.  
Pulled tubing. Tied on to casing and squeezed with 20 sx cement. Casing and backside are full.

GPS: 39.19448 -099.94639

Perfs:

Top	Bot	Thru	Comments
3992	3996		
3971	3974		
3951	3956		
3930	3934		
3878	3880		
3841	3844		
3829	3834		
3798	3802		
3784	3790		

RECEIVED  
KANSAS CORPORATION COMMISSION

AUG 23 2013

CONSERVATION DIVISION  
WICHITA, KS

Remarks: SWIFT CEMENT CO TICKET # 24847

Plugged through: TBG

District: 04

Signed [Signature]  
(TECHNICIAN)

8/29/13

CM

AUG 19 2013