

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-24301-00-01
Spot: SEWNENE Sec/Twnshp/Rge: 22-11S-19W
2210 feet from S Section Line, 940 feet from E Section Line
Lease Name: VINE Well #: 3
County: ELLIS Total Vertical Depth: 3523 feet

Operator License No.: 33922
Op Name: MUSTANG ENERGY CORPORATION
Address: PO BOX 1121
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3522		450 SX
SURF	8.58	340		175 SX
T1	2.875	3500		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/19/2013 9:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: ROD BRIN Company: MUSTANG ENERGY CORP. Phone: (785) 623-0533

Proposed Plugging Method: Ordered 290 sx 60/40 pozmix 4% gel cement; 500 # hulls; 10 sx gel.
PBTD- 3430'
PC at 1627' w/450 sx cement.
GPS: 39.08001 -099.41094
2249' FSL 981' FEL
SE NW NE SE

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/19/2013 10:30 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Quality rigged to 5 1/2" casing with a swedge and mixed and pumped 75 sx cement w/200 # hulls mixed in followed by 10 sx gel followed by 150 sx cement w/300 # hulls mixed in. Pumped to pressure with 500 psi and 400 psi shut in pressure. Rigged to 8 5/8" surface casing and pumped 5 sx cement to pressure with 200 psi and 200 psi shut in pressure.

Perfs:


Top	Bot	Thru	Comments
3509	3511		

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 23 2013

Remarks: QUALITY OILWELL CEMENTING TICKET # 7359

Plugged through: CSG

District: 04

Signed  (TECHNICIAN)

CM

AUG 19 2013