

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-22454-00-00

Spot: SWNWNWSE

Sec/Twnshp/Rge: 25-17S-27W

1997 feet from S Section Line,

2511 feet from E Section Line

Lease Name: ROCKET SCIENCE

Well #: 1

County: LANE

Total Vertical Depth: 4658 feet

Operator License No.: 30742

Op Name: PALOMINO PETROLEUM, INC.

Address: 4924 SE 84TH ST
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comments
--------	------	------------	-------------	----------

SURF	8.625	217		WITH 175 SX CMT
------	-------	-----	--	-----------------

Well Type: DH

UIC Docket No:

Date/Time to Plug: 08/05/2013 1:15 PM

Plug Co. License No.: 33575

Plug Co. Name: WW DRILLING, LLC

Proposal Rcvd. from: MARK BIGGE

Company: WW DRILLING, LLC

Phone: (785) 743-6774

Proposed Plugging Method: 1ST PLUG AT 2040' WITH 50 SX CMT. 2ND PLUG AT 1200' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 50 SX CMT. 4TH PLUG AT 250' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: NATHAN WILLIS

WitnessType: NONE

Date/Time Plugging Completed: 08/05/2013 3:15 PM

KCC Agent: NATHAN WILLIS

Actual Plugging Report:

Perfs:

1ST PLUG AT 2040' WITH 50 SX CMT. 2ND PLUG AT 1200' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 50 SX CMT. 4TH PLUG AT 250' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 14 2013

CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed

Nathan Willis
8/12/13

(TECHNICIAN)

RECEIVED

AUG 12 2013

KCC DODGE CITY

RA32