

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-025-20068-00-00  
Spot: NWNWSENE Sec/Twnshp/Rge: 6-35S-21W  
1407 feet from N Section Line, 1292 feet from E Section Line  
Lease Name: TUTTLE Well #: 6  
County: CLARK Total Vertical Depth: 5704 feet

Operator License No.: 32192  
Op Name: PRIDE ENERGY COMPANY, A GENERA  
Address: P O BOX 701950  
TULSA, OK 74170

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	5703	1440	WITH 150 SX CMT
SURF	8.625	615		WITH 100 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/24/2013 8:00 AM  
Plug Co. License No.: 34235 Plug Co. Name: AMIGOS WELL SERVICE INC.  
Proposal Rcvd. from: EDGAR SANCHEZ Company: AMIGOS WELL SERVICE INC. Phone: (620) 388-6229

Proposed Plugging Method: CIBP @ 5465' WITH 4 SX CMT. PLUG AT 920' WITH 15 SX GEL & 50 SX CMT. PLUG AT 640' WITH 50 SX CMT. PLUG AT 250' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE  
Date/Time Plugging Completed: 07/24/2013 5:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SANDED TO 50' ABOVE THE PERFS WITH 4 SX CMT. 1ST PLUG AT 915' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 640' WITH 50 SX CMT. 3RD PLUG AT 300' WITH 40 SX CMT. CMT CIRCULATED. TOPPED OFF WITH 4 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5546	5548		MORROW B
5527	5529		MORROW A
5515	5522		MORROW A

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

RECEIVED  
KANSAS CORPORATION COMMISSION

AUG 26 2013

CONSERVATION DIVISION  
WICHITA, KS

District: 01

RECEIVED

AUG 22 2013

KCC DODGE CITY

Signed

Eric MacLaren  
9/09/13 (TECHNICIAN)