

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-19039-00-00
Spot: SWNENENE Sec/Twnshp/Rge: 10-32S-7E
4877 feet from S Section Line, 351 feet from E Section Line
Lease Name: BEAMER Well #: 3
County: COWLEY Total Vertical Depth: 2198 feet

Operator License No.: 33711

Op Name: B-C STEEL, LLC

Address: 209 N FRY ST
YATES CENTER, KS 66783

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2195	348	100 SX
SURF	8.625	62		75 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 06/18/2013 8:00 AM

Plug Co. License No.: 31074

Plug Co. Name: BRAKE, JOE DBA BRAKE INC.

Proposal Rcvd. from: RON WHITEMAN

Company: GENDOR OIL CO

Phone: (620) 467-2615

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER

Witness Type: PARTIAL

Date/Time Plugging Completed: 07/10/2013 5:00 PM

KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED WELL BACK @ 2060', DUMP BAILED 4 SXS CEMENT ON TOP. TAGGED BOTTOM PLUG @ 2036'. CUT CASING @ 348', LAYED DOWN 4 1/2" CASING. 7-10-2013, RIH W/TBG @ 350', BRAKE OIL PUMPED 140 SXS 60/40 POZMIX TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM 7-10-2013. DANIES READY MIX TICKET #028623.

Perfs:

Top	Bot	Thru	Comments
2137	2152	CSG	

Remarks: COMPLIANCE / 10 YR RULE

Plugged through: TBG

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 23 2013

CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed

DUANE KRUEGER
8/28/13 (TECHNICIAN)

JK