

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-19040-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 10-32S-7E
4956 feet from S Section Line, 1002 feet from E Section Line
Lease Name: BEAMER Well #: 5
County: COWLEY Total Vertical Depth: 2185 feet

Operator License No.: 33711

Op Name: B-C STEEL, LLC

Address: 209 N FRY ST
YATES CENTER, KS 66783

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2185	375	100 SX
SURF	8.625	72		60 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 06/19/2013 8:00 AM

Plug Co. License No.: 31074

Plug Co. Name: BRAKE, JOE DBA BRAKE INC.

Proposal Rcvd. from: RON WHITEMAN

Company: GENDOR OIL CO.

Phone: (620) 467-2615

Proposed
Plugging
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER

WitnessType: PARTIAL

Date/Time Plugging Completed: 07/02/2013 5:00 PM

KCC Agent: DAN FOX

Actual Plugging Report:

TAGGED TD @ 2135'. SANDED WELL BACK @ 2085', DUMP BAILED 4 SXS CEMENT ON TOP. TAGGED BTM PLUG @ 2060'. 7-1-2013, RIH ON WIRELINE CUT CASING @ 375', LAYED DOWN CASING. 7-2-2013. RIH W/TBG @ 350', BRAKE OIL PUMPED 140 SXS 60/40 POZMIX TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM 7-2-2013. DANIELS READY MIX TICKET #028573.

Perfs:

Top	Bot	Thru	Comments
2134	2144	CSG	

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: COMPLIANCE/ 10 YR RULE

Plugged through: TBG

AUG 23 2013
CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed

Duane Krueger
8/23/13
(TECHNICIAN)

JK