

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-19042-00-00  
Spot: SWSWNE Sec/Twnshp/Rge: 10-32S-7E  
2917 feet from S Section Line, 2320 feet from E Section Line  
Lease Name: BEAMER Well #: 12  
County: COWLEY Total Vertical Depth: 2443 feet

Operator License No.: 33711

Op Name: B-C STEEL, LLC

Address: 209 N FRY ST  
YATES CENTER, KS 66783

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2441	375	160 SX
SURF	8.625	115		75 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 06/28/2013 8:00 AM

Plug Co. License No.: 31074

Plug Co. Name: BRAKE, JOE DBA BRAKE INC.

Proposal Rcvd. from: RON WHITEMAN

Company: GENDOR OIL CO

Phone: (620) 467-2615

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER

WitnessType: PARTIAL

Date/Time Plugging Completed: 07/02/2013 5:00 PM

KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED WELL BACK 2 2050', DUMP BAILED 5 SXS CEMENT ON TOP. TAGGED BOTTOM PLUG @ 2020'. RIH ON WIRELINE CUT CASING @ 375', LAYED DOWN 12 JOINTS 5-1/2" CASING. RIH W/TBG @ 350', BRAKE OIL PUMPED 140 SXS 60/40 POZMIX TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM 7-2-2013. DANIELS READY MIX TICKET #028548 & 28570.

Perfs:

Top	Bot	Thru	Comments
2104	2112	CSG	

RECEIVED  
KANSAS CORPORATION COMMISSION

Remarks: COMPLIANCE / 10 YR RULE

**AUG 23 2013**

Plugged through: TBG

CONSERVATION DIVISION  
WICHITA, KS

District: 02

Signed

Duane Krueger  
8/23/13 (TECHNICIAN)

JK