

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-20896-00-00
Spot: SWNESWNE Sec/Twnshp/Rge: 10-32S-7E
3582 feet from S Section Line, 1662 feet from E Section Line
Lease Name: BEAMER Well #: 16
County: COWLEY Total Vertical Depth: 2190 feet

Operator License No.: 33711
Op Name: B-C STEEL, LLC
Address: 209 N FRY ST
YATES CENTER, KS 66783

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2200		100 SX
SURF	7	200		75 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/24/2013 8:00 AM
Plug Co. License No.: 31074 Plug Co. Name: BRAKE, JOE DBA BRAKE INC.
Proposal Rcvd. from: RON WHITEMAN Company: GENDOR OIL CO Phone: (620) 467-2615

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 07/02/2013 5:00 PM KCC Agent: DAN FOX

Actual Plugging Report:

TAGGED TD @ 2170', SANDED WELL BACK @ 2075', DUMP BAILED 4 SXS CEMENT ON TOP. TAGGED BOTTOM PLUG @ 2040'. 6-25-2013, RIH ON WIRELINE CUT CASING @ 365', LAYED DOWN CASING. 7-2-2013. RIH W/TBG @ 350', BRAKE OIL PUMPED 120 SXS 60/40 POZMIX TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM 7-2-2013. DANIELS READY MIX TICKET #028581.

Perfs:

Top	Bot	Thru	Comments
2136	2146	CSG	

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: COMPLIANCE / 10 YEAR RULE

Plugged through: TBG

AUG 23 2013

CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed Duane Krueger
8/29/13 (TECHNICIAN)

SK