

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-20059-00-00
Spot: SWSENW Sec/Twnshp/Rge: 36-31S-4E
2970 feet from S Section Line, 3630 feet from E Section Line
Lease Name: LOREN HOLT A Well #: 4
County: COWLEY Total Vertical Depth: 2414 feet

Operator License No.: 34320
Op Name: LASSO ENERGY LLC
Address: PO BOX 465
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2412		125 SX
SURF	8	200		
SURF	8.625	220		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/12/2013 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE INC Phone: (620) 938-2943

Proposed Plugging Method: AS PER KCC RULES & REGS / 25 SXS ON BOTTOM - 270'-0" CIRC CEMENT

Plugging Proposal Received By: DUANE KRUEGER WitnessType: NONE
Date/Time Plugging Completed: 05/08/2013 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED WELL BACK @ 2310', RIH W/TBG @ 2270', COPELAND ACID MIXED & PUMPED 15 SXS 60/40 POZMIX 4% GEL & DISPLACED IN CASING. 4-15-2013, RIH ON WIRELINE SHOT SQUEEZE HOLES @ 270'-271'. RIH W/TBG @ 280', COPELAND ACID MIXED & PUMPED 110 SXS 60/40 POZMIX 4% GEL TO SURFACE, LAYED DOWN TBG, SWEDGED INTO 5 1/2" CSG & PUMPED 80 SXS 60/40 POZMIX 4% GEL (185 SXS TOTAL). WELL ON VACUUM. 5/7/2013, TAGGED CEMENT @1600'. 5-7-2013, RIH W/TBG @ 250', COPELAND ACID LOADED HOLE W/8 BBL FLUID, MIXED & PUMPED 30 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. TOPPED WELL BACK TO SURFACE W/3 SXS. CEMENT TICKET #38505.

Perfs:

Top	Bot	Thru	Comments
2367	2371	CSG	

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 16 2013

Remarks:

Plugged through: TBG

CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed DUANE KRUEGER
8/21/13 (TECHNICIAN)