

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-20388-00-00
Spot: NESWNWNE Sec/Twnshp/Rge: 1-20S-2W
4400 feet from S Section Line, 2200 feet from E Section Line
Lease Name: JANTZ Well #: 1
County: MCPHERSON Total Vertical Depth: 3400 feet

Operator License No.: 5631
Op Name: LOEWEN OPERATOR, INC.
Address: 208 S MAIN PO BOX 335
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3010		
PROD	5.5	3399		150 SXS CMT
SURF	8.625	150		100 SXS CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/07/2011 12:00 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: CARMON R. DECKER Company: _____ Phone: (816) 223-3712

Proposed Plugging Method: AS PER KCC DISTRICT 2 RULES & REGS

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 02/07/2011 12:00 AM KCC Agent: HUNTER CLARK

Actual Plugging Report:

RIGGED UP RAN BIT ON TUBING TO OBSTRUCTION AT 452' RIGGED SWIVEL UP DRILLED TO A DEPTH OF 459' TRIPPED BIT OUT THE HOLE. RAN TUBING TO 450' PUMPED 65 SKS 60/40 4%, CIRCULATED TO SURFACE. CUT OFF SURFACE PIPE AND RAN 1" DOWN BACKSIDE TO 149' CIRCULATED TO SURFACE, PULLED 1" OUT =, THEN RAN THE 1" DOWN 5.5 TAGGED CEMENT AT 100' TOPPED OF CASING TO SURFACE USED 245 SKS OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
2944	2958		MISSISSIPPI

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: CEMENT TICKET #C37090 COPLAND BURTON

AUG 13 2013

Plugged through: TBG

CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed

HAWCH PIRELLI
8/20/13 (TECHNICIAN)