

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-20827-00-00  
Spot: SESESESE Sec/Twnshp/Rge: 2-16S-12W  
295 feet from S Section Line, 295 feet from E Section Line  
Lease Name: SCHAUF A TWIN Well #: 7  
County: BARTON Total Vertical Depth: 3020 feet

Operator License No.: 5259  
Op Name: MAI OIL OPERATIONS, INC.  
Address: 8411 PRESTON RD STE 800  
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2974		100 SX
SURF	8.625	320		200 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/01/2013 9:30 AM  
Plug Co. License No.: 7049 Plug Co. Name: RAPID WELL SERVICE, INC.  
Proposal Rcvd. from: BRENT HOMEIER Company: M I A OIL OPERATION Phone: (785) 445-2353

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/500 # hulls and 9 sx gel.  
Perforations: 1350', 750' and 300'.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/01/2013 4:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2895' and pumped 5 sx gel followed by 50 sx cement w/50 # hulls.  
Pulled tubing to 1386' and pumped 80 sx cement. Cement circulated out back side. Shut in and pumped 110 sx cement. Cement circulated out the braden head.  
POOH. Pumped 50 sx cement and cement circulated out the braden head. Shut down. Cement down 12'.

GPS: 38.68213 -098.60984

Perfs:

Top	Bot	Thru	Comments
2881	2923		

Remarks: ALLIED CEMENTING TICKET # 60554

Plugged through: TBG

District: 04

Signed

Ray A. Dinkel  
8/1/13

(TECHNICIAN)

CM

RECEIVED  
KANSAS CORPORATION COMMISSION

Form CP-2/3

AUG 05 2013

AUG 09 2013

CONSERVATION DIVISION  
WICHITA, KS