

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-03640-00-00  
Spot: W2SWNE Sec/Twnshp/Rge: 21-9S-16W  
3300 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: DORR UNIT Well #: 902  
County: ROOKS Total Vertical Depth: 3464 feet

Operator License No.: 6569  
Op Name: CARMEN SCHMITT, INC.  
Address: PO BOX 47  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3463		
SURF	8.625	260		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/06/2013 9:00 AM  
Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.  
Proposal Rcvd. from: CURTIS HITSCHMANN Company: CARMEN SXHMITT, INC. Phone: (620) 793-2540

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
Tubing parted at 928'. Tubing stuck in hole.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/06/2013 10:00 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 928' and pumped 175 sx cement w/100 # hulls.  
Pulled tubing and pumped 25 sx cement. Pressured to 300 psi.  
Hooked to 8 5/8"x5 1/2" annulus and pumped 25 sx cement. Shut in pressure 200 psi.  
GPS: 39.25818N -099.11131W

Perfs:

Top	Bot	Thru	Comments
3300	3307		
3253	3256		
3208	3212		
3197	3200		

Remarks: COPELAND ACID AND CEMENTING TICKET # 41355

Plugged through: TBG

RECEIVED  
KANSAS CORPORATION COMMISSION

AUG 23 2013

CONSERVATION DIVISION  
WICHITA, KS

District: 04

Signed

8/29/13

Pat Bedore

(TECHNICIAN)

CM

AUG 19 2013