

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-03591-00-00
Spot: NENW Sec/Twnshp/Rge: 3-9S-16W
feet from Section Line, feet from Section Line
Lease Name: GAMBLE Well #: 3
County: ROOKS Total Vertical Depth: 3152 feet

Operator License No.: 6569
Op Name: CARMEN SCHMITT, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3115		
SURF	10.75	70		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/08/2013 11:00 AM
Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.
Proposal Rcvd. from: CURTIS HITSCHMANN Company: CARMEN SCHMITT, INC. Phone: (620) 793-2540

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Tubing parted at 2351'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/08/2013 1:20 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perforated at 800', 1230' and 1800'.
Ran tubing to 2351' and pumped 125 sx cement w/250 # hulls.
Pulled tubing to 1300' and pumped 160 sx cement w/150 # hulls to circulate cement to surface.
Pulled tubing. Hooked to 5 1/2" casing and pumped 50 sx cement. Shut in pressure 400 psi.
Hooked to 10"x5 1/2" annulus and pumped 50 sx cement. Shut in pressure 150 psi.

GPS: 39.3537N -099.09721W

Perfs:

Remarks: COPELAND ACID AND CEMENTING TICKET # 41159

Plugged through: TBG

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 23 2013

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed

8/29/13

Pat Bedore

(TECHNICIAN)

CM

AUG 19 2013