

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
DEC 8 - 1972
12-8-72
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name The National Oil Company
Complete Address Suite 550 O. W. Garvey Bldg., Wichita, Kansas
Lease Name V. Smith Well No. 1
Location C NE SW SW Sec. 36 Twp. 19 Rge. (E) (W) 20
County Rush Total Depth 3800'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor H-30 Drlg.
Address Wichita, Kansas License No.
Operation Completed: Hour 2:30 P Day 7 Month 12 Year 1972

The above well was plugged as follows:

RTD 3800' 8 5/8 csg set at 316' ~~cmt.~~ Cmt. Mat. 50-50 poz cmt W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 ax
cmt thru drill pipe. Heavy mud to 300' set cementing plug and displaced 20 sx cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: L. J. Murray
Well Plugging Supervisor

INVOICED

DATE 12/8/72INV. NO. 6709-11