

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

JUN 04 1978
6-2-78

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -165-01002-0000 (of this well)

Operator's Full Name Mull Drilling Co., Inc.

Complete Address 415 Page Ct., 220 W. Douglas. Wichita, Kansas 67202

Lease Name West Well No. 1

Location NE NW NW Sec. 31 Twp. 19 Rge. (E) (W) 19

County Rush Total Depth 4370'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor CO. Tools by Halliburton

Address License No.

Operation Completed: Hour 12:30 P Day 31 Month 5 Year 1978

The above well was plugged as follows:

Total Depth 4370' 8. 5/8 csg set 355' cwc 200 sk.

4 1/2 csg set 4369' cw 125 sk cem. with top perf. (4163')

4 1/2 csg sq. W/300 sk cem. from 800'-700' & circ. to surface. No pipe recovered.

Halliburton Cementing Co. mixed & pumped down annulus with 35 sk cem.

Down 4 1/2 csg with 50 sk cem -displaced with 25 sk gel & water & capped with cementing

plug & 40 sk cem. & shutin. FPP 500 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Marney
Well Plugging Supervisor

DATE 6-2-78

INV. NO. 7421-W