

15135-26466-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
AUG 30 1971
CONSERVATION DIVISION
Wichita, Kansas
8-30-71

Operator's Full Name Okmar Oil Company
Complete Address 1130 Vickers KSB&T Bldg., Wichita, Kansas
Lease Name Vera Well No. 1
Location C SE NW Sec. 9 Twp. 16 Rge. (E) (W) 26
County Ness Total Depth 4600'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Strata Drlg.
Address Wichita, Kansas License No.
Operation Completed: Hour 9:15 P Day 23 Month 8 Year 1971

The above well was plugged as follows:

RTD 4600' 5/8 csg set at 311' cwc Cmt. Mat. 100 sk reg poz W/4% added gel.
Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 280' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 8-31-71

INV. NO. 4242-U