

15-077-30092-00-00

R

Form CP-3  
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

MAY 26 1966  
05-26-1966  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Pickrell Drilling Company

Complete Address: 705 Fourth National Bank Bldg., Wichita, Kansas

Lease Name Rutledge "A" Well No. # 1

Location C SW NW Sec. 8 Twp. 31 Rge. 7 (E) (W) W

County Harper Total Depth 4827'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Pickrell Drilling Company

Address: 705 Fourth National Bank Bldg., Wichita, Kansas License No.     

Operation Completed: Hour 3:00PM Day 22nd Month May Year 1966

The Above well was plugged as follows:

204' of 8 5/8" surface pipe, cement circulated with 170 sacks. Hole  
was filled with drilling mud to 200', 1st cementing plug, bridged with  
2 sacks of dry cement and 1/2 sack of hulls on fluid at 200', and cemented  
with 23 sacks. Hole was filled with drilling mud to 40', 2nd cementing  
plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid at  
40', and cemented with 9 sacks to the base of the cellar. Rat hole  
bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5-26-66

INV. NO. 3291-W

Signed: Archie Elving  
Well Plugging Supervisor