

15-055-10770-0000

Form CP-3
Rev. 6-26-62

KANSAS

af
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 8 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Texaco Inc.

Complete Address: 614 Bitting Bldg., Wichita, Kansas 67202

Lease Name Veda Loomis Well No. 1

Location C SW SW Sec. 30 Twp. 21 Rge. 33 ~~(E)~~ ^{XX} (W)

County Finney Total Depth 4820'

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A X

Other well as hereafter indicated: None

Plugging Contractor: Sargents Casing Pulling Co.

Address: Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 1:00PM Day 2 Month 9 Year 1969

The Above well was plugged as follows:

8 5/8" to 638' circulated w/ cement. 4 1/2" to 4820' cemented.

Top perforations 4545' Plug bottom w/ 15 sacks cement 1/4

Top of cement 4420' Mud 4420' to 650'

Spotted 40 sacks 650' to 550' Mud 550' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'. Company Pump

Pulled 2502' of 4 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edgar F. Eves
Well Plugging Supervisor

DATE 9/8/69
INV. NO. 419-W