

State of Kansas



15135-70897-06006

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 20 1974  
6-20-74  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Moore of G & G Drlg. has this date requested permission to plug the following described well:

Mr. Moore guarantees payment of the plugging fee.

Operator's full Name: Dane G. Hansen Trust

Complete Address: Box 187, Logan, Ks.

Lease Name: Holmes "A" Well No. 1

Location: NW NE SW Sec. 15 Twp. 16 Rge. (E)(W) 26

County: Ness Total Depth 4564 Oil Well     

Gas Well      Input Well      SWD Well      D & A XX Lost Hole     

Mr. Moore was instructed to plug the well as follows:  
Gun pits, circulate heavy mud, set cementing plug at 800' and displace  
70 sk cmt thru drill pipe. Heavy mud to 185' set cementing plug and  
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Red F. Massey  
Conservation Division Agent