

State of Kansas



15:135:301640000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

RECEIVED
CONSERVATION DIVISION
WICHITA, KANSAS

APR 18 1966
4-18-66
CONSERVATION DIVISION
Wichita, Kansas

APR 20 1966

CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Helberg of EMPIRE DRILLING CO has this date requested permission to plug the following described well:

Mr. Helberg guarantees payment of the plugging fee.

Operator's full Name: EMPIRE DRILLING CO

Complete Address: 1050 Fourth Nat Bank Wichita, Ks

Lease Name: BAUSINGER Well No. 1

Location: 0-NW-NE Sec. 5 Twp. 16 Rge. 26 (E)(W) X

County Ness Total Depth 4511 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Helberg was instructed to plug the well as follows:

~~set pits circulate hole with heavy mud, set cementing plug at 540 ft.,
and displace 20 sac cement thru drill pipe, heavy mud to 120 ft., set
cementing plug and displace 20 sac cement thru drill pipe, heavy mud
to 40 ft., set cementing plug, 1/2 sac bulls and 10 sac cement, cementing
to base of collar. Plug rat hole with two sac cement.~~

Very truly yours,

Leo Murray
Conservation Division Agent