



15135-30135-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

DEC 14 1965
12-14-65
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Suede Helberg of Empire Bldg Co. has this
date requested permission to plug the following described well:

Mr. Helberg guarantees payment of the plugging fee.

Operator's full Name: Empire Bldg Co.

Complete Address: 650 4th Natl Bldg Wichita Kansas

Lease Name: Armstrong Well No. 3

Location: E-N-E-Sw 1/4 Sec. 7 Twp. 16 Rge. 26 (E) (W)

County Ness Total Depth 4568 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Helberg was instructed to plug the well as follows:
Jett pits circulate hole with heavy mud, set cementing plug at 540 ft.
and displace 20 sac cement thru drill pipe, heavy mud to 100 ft.,
set plug and displace 25 sac cement, heavy mud to 40 ft., set
plug 1/2 sac hulls and 20 sac cement, cementing to base of collar.

Very truly yours,
Gilbert P. Leiker
Gilbert P. Leiker
Conservation Division Agent