

State of Kansas



CP2

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 8 - 1972  
12-8-72  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Heffner of National Oil has this

date requested permission to plug the following described well:

Mr. Hefner guarantees payment of the plugging fee.Operator's full Name: The Nat'l Oil Co.Complete Address: Suite 550, O. W. Garvey Bldg., Wichita, Ks.Lease Name: V. Smith Well No. 1Location: C NE SW SW Sec. 36 Twp. 19 Rge. (E)(W) 20County: Rush Total Depth 3800' Oil Well Gas Well  Input Well  SWD Well  D & A XX Lost Hole Mr. Hefner was instructed to plug the well as follows:Gun pits, circulate heavy mud, set cementing plug at 660' and displace70 sk cmt thru drill pipe. Heavy mud to 300' set cementing plug anddisplace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing plug,1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo F. Mansup  
Conservation Division Agent