

API NUMBER 15-135-23862000

LEASE NAME Baker

WELL NUMBER 1-10

2060 Ft. from (S) Section Line

330 Ft. from (E) Section Line

SEC. 10 TWP. 16 RGE. 26 (E) or (W)

COUNTY Ness

Date Well Completed 3-21-97

Plugging Commenced 3-21-97

Plugging Completed 3-21-97

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Coes. Div.  
 office within 30 days.

LEASE OPERATOR Cross Bar Petroleum, Inc.

ADDRESS 151 Main, Suite 630 Wichita, Kansas 67202-1407

PHONE (316) 265-2279 OPERATORS LICENSE NO. 4243

Character of Well D & A

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on March 20, 1995 (date)

by Richard Lacey (Dodge City) (XCC District Agent's Name).

Is ACO-1 filed? by operator if not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4570'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
surface		0	357'	8 5/8"	357'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set

50 sx. @ 2080', 80 sx. @ 1300', 40 sx. @ 700', 50 sx. @ 380', 10 sx. @ 40', 15 sx. in rat  
Total: 245 sx. 60/40 Pozmix, 6% Gel, 1/4# floreal Allied Cementing plugged. hole

Name of Plugging Contractor L. D. Drilling, Inc. License No. 6039

Address R.R. 1 Box 183 B Great Bend, Kansas 67530


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Cross Bar Petroleum, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

L.D. Davis (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) L.D. Davis

(Address) R.R. 1 Box 183 B Great Bend, KS. 67530



SUBSCRIBED AND SWORN TO before me this 24th day of March, 19 95

Bessie M. DeWerff  
 Notary Public  
 Bessie M. DeWerff

My Commission Expires: 5-20-97

USE ONLY ONE SIDE OF EACH FORM