

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-23,518-0000

LEASE NAME BAKER "BD"

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #1

1650' Ft. from S Section Line

440' Ft. from E Section Line

LEASE OPERATOR VESS OIL CORPORATION

SEC. 10 TWP. 16 SRGE. 26 (X) or (W)

ADDRESS 8100 E. 22nd North, Bldg. 300 Wichita, Ks. 67226

COUNTY Ness

PHONE#(316) 682-1537 OPERATORS LICENSE NO. 5030

Date Well Completed 11-13-90

Character of Well D&A

Plugging Commenced 11-13-90

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11-13-90

The plugging proposal was approved on November 13, 1990 (date)

by Steve Durant (KCC District Agent's Name).

Is ACO-1 filed? by operator If not, Is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.O. 4548'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>surface</u>		<u>0</u>	<u>256'</u>	<u>8 5/8"</u>	<u>256'</u>	<u>none</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

50 sx. @ 2060', 80 sx. @ 1200', 50 sx. @ 660', 40 sx. @ 300', 10 sx. @ 40'

15 sx. in rathole Total: 245 sx. 60/40 Pozmix, 6% gel, 1 sx. flo-seal

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co. License No. _____


Address Great Bend, Ks.

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Greg Davidson

STATE OF Kansas COUNTY OF Barton, ss.

Greg Davidson (Employee of Operator) or ~~Notary Public~~ of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



NOV 27 1990
11-27-90
CONSERVATION DIVISION
Wichita, Kansas
(Signature) Greg Davidson
(Address) Great Bend, KS. 67530

SUBSCRIBED AND SWORN TO before me this 26th day of November, 1990

My Commission Expires: 5-20-93

Bessie M. DeWerff
Notary Public
Bessie M. DeWerff

15.135.23518.0000

DRILLER'S WELL LOG

COMMENCED: 11-06-90
COMPLETED: 11-13-90

VESS OIL CORPORATION
BAKER #1
110' W SE NE SE Sec. 10-16S-26W
Ness County, Kansas

- 0 - 256 Surface
- 256 - 565 Clay & Shale
- 565 - 1875 Clay-shale & sand streaks
- 1875 - 2031 Shale W/sand streaks
- 2031 - 2074 Anhy
- 2074 - 2570 Shale W/lime
- 2570 - 2800 Shale
- 2800 - 4115 Lime & Shale
- 4115 - 4551 Lime
- 4551 R.T.D

ELEVATION: 2611 GL 2616 KB

FORMATION DATA:

Anhy	2039 (+577)	2074(+542)
Heebner	3883 (-1267)	
Lansing	3923 (-1307)	
Stark	4170 (-1554)	
B K/C	4227 (-1611)	
Fort Scott	4437 (-1821)	
Cherokee	4468 (-1852)	
Mississippi	4535 (-1919)	
RTD	4551 (-1935)	

SURFACE CASING:

8 5/8" set @ 256' W/160 sx. 60/40 Pozmix,
2% Gel, 3% CC

AFFIDAVIT

NOV 27 1990

NOV 27 1990


CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
COUNTY OF BARTON)^{ss}

GREG DAVIDSON of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Greg Davidson
Greg Davidson

Subscribed and sworn to before me this 26th day of November, 1990.



Bessie M. DeWerff
Notary Public: Bessie M. DeWerff

My Commission Expires: 5-20-93