


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

15-135-20793-0000

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202



Locate well correctly on above  
Section Plot

Ness County, Sec. 10 Twp. 16S Rge. 26 E/W  
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{4}$ " or footage from lines  
NE SE SE

Lease Owner Patrick Petroleum Corporation  
Lease Name Baker Well No. 1  
Office Address 200 E. First, Suite 414, Wichita, Ks.  
Character of Well (Completed as Oil, Gas or Dry Hole) 67202  
oil

Date Well completed Sept. 30 1973  
Application for plugging filed May 20 1977  
Application for plugging approved 1977  
Plugging commenced July 6 1977  
Plugging completed July 15 1977  
Reason for abandonment of well or producing formation  
depleted

If a producing well is abandoned, date of last production  
19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey  
Producing formation Depth to top Bottom Total Depth of Well 4537'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENTS	FROM	TO	SIZE	PUT IN	PULLED OUT
			277'	8 5/8"	277'	none
			4534'	5 1/2"	4534'	2006.04

RECEIVED  
STATE CORPORATION COMMISSION  
7-22-77  
JUL 22 1977  
CONSERVATION DIVISION

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to  
\_\_\_\_\_ feet for each plug set.

Sanded back to 4500' and dumped 4 sacks of cement.

Halliburton Services plugged well pumping in 1 sack of hulla, 32 sacks of  
gel and 140 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor PIPE PULLERS, INC.  
Box 128, Ellinwood, Kansas 67526

STATE OF KANSAS COUNTY OF BARTON ss.  
Evelyn Roth (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the  
above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth  
Ellinwood, Kansas  
(Address)

Subscribed and Sworn to before me this 19th day of July, 1977

My commission expires

JENNY KASSELMAN  
NOTARY PUBLIC  
BARTON COUNTY, KANSAS  
MY COMM. EXP. JULY 16, 1978

Jenny Kasselmann  
Notary Public.

DRILLERS LOG

#1 Baker

15135-20793-6000

CASING RECORD:  
277.76' of new 8-5/8"  
surface casing.

COMPANY: Patrick Petroleum Corp.

DESCRIPTION: NE SE SE  
Section 10-16S-26W  
Ness County, Kansas

CONTRACTOR: Strata Drilling, Inc.

TOTAL DEPTH:  
4537'

COMMENCED: September 19, 1973

COMPLETED: September 30, 1973

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale & Clay	0	295	Ran 277.76' of new 8-5/8" surface casing; set and cemented at 283.76' with 170 sacks of common cement, 2% gel and 3% C. C. Plug down at 11:15 P. M. September 19, 1973.
Shale	295	1300	
Sand & Shale	1300	2000	
Shale	2000	2335	
Lime & Shale	2335	4159	
Lime	4159	4185	
Lime & Shale	4185	4244	
Lime	4244	4413	
Lime & Shale	4413	4520	
Lime	4520	4537	

ROTARY TOTAL DEPTH: 4537'

Ran electric log.

MAY 25 1977  
Strata Drilling, Inc.  
Ness County, Kansas

Used 5 1/2" casing set and cemented at 4534' with 150 sacks of 50-50 pozmix, 18% salt. Plug down at 12:13 A. M. September 30, 1973.

STATE OF KANSAS )  
                          ) ss.  
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Charles W. Steincamp  
Charles W. Steincamp, President

Subscribed and sworn to before me this 1st day of October, 1973.

My Commission Expires:

December 14, 1973

Elaine H. Taylor  
Elaine H. Taylor, Notary Public