

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Ness County. Sec. 18 Twp. 16S Rge. 26W (#) (W)

Location as "NE/CNWxSWx" or footage from lines C SW SW

Lease Owner Cameron Funk

Lease Name McBee Well No. 1

Office Address 702 Union Center, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 2-25-66 19

Application for plugging filed 2-25-66 19

Application for plugging approved 2-25-66 19


Plugging commenced 2-25-66 19

Plugging completed 2-25-66 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4600 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	108'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mudded to 600', set plug with 20 sacks cement  
Mudded to 140', set plug with 1/2 sk. hulls and 20 sacks cement  
Mudded to 40', set plug with 1/2 sk. hulls and 10 sacks cement  
set 2 sacks cement in rathole

*Rec'd  
3-1-66*

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.

Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.

Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Leslie Kite*

P. O. Box 486, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 28th day of February, 1966

My commission expires April 1, 1967

*Ulanda Nichols*  
Ulanda Nichols Notary Public.

15:35-30185-0000

DRILLER'S LOG

COMPANY: Cameron Funk  
 CONTRACTOR: LEBEN DRILLING, INC.  
 FARM: McBEE #1  
 LOCATION: C SW SW Sec. 18-16S-26W  
 NESS COUNTY, KANSAS  
 COMMENCED: 2-15-66  
 COMPLETED: 2-25-66

-----

0	108	Clay, Shale
108	1300	Shale
1300	1350	Sand Streaks
1350	1505	Shale
1505	2075	Shale, Shells
2075	2155	Lime
2155	2620	Shale, Lime
2620	2785	Shale, Lime Streaks
2785	2940	Lime, Shale
2940	3410	Lime
3410	3610	Lime, Shale
3610	3730	Shale, Lime
3730	3945	Lime, Shale
3945	4550	Lime
4550	4567	Lime, Chert
4567	4600	Lime
	<u>4600</u>	<u>RTD - D. &amp; A.</u>

RECEIVED  
STATE CORPORATION COMMISSION

MAR 1 1966

CONSERVATION DIVISION  
Wichita, Kansas

-----

8 5/8" used surface casing set @ 108' cemented with 100 sacks 60-40  
 Sunset Posmix 2% Gel

-----

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the McBee #1 well, located C SW SW of Section 18, Township 16 South, Range 26 West, Ness County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS )  
 ) SS  
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, as of this 28th day of February, 1966.

Ulanda Nichols

Ulanda, Nichols

My Commission Expires:  
 April 1, 1967