

LEASE NAME Carlson

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 17 TWP. 16 RGE. 26 MEMPHIS

COUNTY Ness

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

EASE OPERATOR Zenith Drilling Corporation

ADDRESS 1861 N. Rock Road Wichita, Ks. 67206

PHONE# (316) 684-9777 OPERATORS LICENSE NO. 5141

Date Well Completed

Character of Well Oil

Plugging Commenced 1-3-96

(Oil, Gas, O&A, SMD, Input, Water Supply Well)

Plugging Completed 1-5-96

The plugging proposal was approved on (date)

 (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4630'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	325'	none
				4 1/2"	4608'	1783'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug are used, state the character of same and depth placed, from feet to feet each set
Plugged off bottom with sand to 4480' and 4 sacks cement. Shot pipe at 2800', @2500', and 2000'. Pulled to 1900', pumped 50 sacks cement displaced with gel. csg. hung up. shot pipe at 1600' came loose. Pulled to 1200' pumped 80 sacks cement. Pulled to 600' pumped 40 sacks cement. Pulled to 360' pumped 40 sacks cement. Pulled rest of casing, topped off with 10 sacks cement. (60/40 6% gel) Plugging complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 209 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mike's Testing & Salvage, Inc. Chase, Ks.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P.O. Box 209 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 12th day of January, 19 96

Irene Herzeberg
 Notary Public

My Commission Expires:
 USE ONLY ONE SIDE OF EACH FORM

