

API NUMBER 15-135-21354-0000

LEASE NAME Jennings

WELL NUMBER 1

         Ft. from S Section Line

NW SW NW Ft. from E Section Line

SEC. 14 TWP. 16 RGE. 26 (E) or (W)

COUNTY Ness

Date Well Completed         

Plugging Commenced 2-21-94

Plugging Completed 2-21-94

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Berexco, Inc.

ADDRESS Box 723 Hays, Kansas 67601

PHONE# (913) 628 6101 OPERATORS LICENSE NO. 5363

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-21-94 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed?          If not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.O. 4514

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface	0	335	8 5/8		None
	Casing	0	4508	4 1/2		None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from          feet to          feet each section.  
Run tubing to 4510.22'. Mix 23 sks gel followed by 25 sk. 60/40 box, 10% gel with 100# hulls. Pull 108 its. to 1216.56'. Mix 110 sk. 60/40 pos 6% gel. Circulate cement to surface. Pull tubing. Mix 80 sk. 60/40 pos. 6% gel down 4 1/2 400# max. 100# shut in. Hook to 8 5/8 mix 10 sk. 60/40 nosmix 6% gel. Max. pressure 500#. Shut in 500#

Name of Plugging Contractor Berexco, Inc. License No. 5363

Address Rx 723 Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berexco, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Mr. Ted Crawford

(Employee of Operator) or (Operator)


above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated herein, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Mr. Ted Crawford

(Address) Box 723 Hays, Mo 67601

Subscribed and sworn to before me this 25 day of February, 19 94

Rosemary Smith  
 Notary Public



My Commission Expires: 5-1-1995

USE ONLY ONE SIDE OF EACH FORM