

1 051783

2-21

API NUMBER 15- 135-21,354-0000

TO: STATE CORPORATION COMMISSION CONSERVATION DIVISION - PLUGGING SECTION 200 COLORADO DERBY BUILDING WICHITA, KANSAS 67202

NW SW NW, SEC. 14, T 16 S, R 26

3630 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363

Lease Name Jennings Well # 1

County Ness

Well Total Depth 4514 146.71

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 335

Operator: BEREXCO, INC. Name: P.O. Box 723 Address: Hays, KS 67601

Abandoned Oil Well X Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing Co. Inc. License Number

Address P.O. Box 31, Russell, KS 67665-0031

Company to plug at: Hour: 10:30 a.m. Day: 21 Month: 2 Year: 19 94

Plugging proposal received from Bob Grant

(company name) BEREXCO, INC. (phone) 913-628-6101

1st plug run tubing to 4508' and pump 23 sx gel and 25 sx cement with 100 lbs. hulls, 4 1/2" at 4510' w/100 sx cement, Open hole 4508-14', Squeezed at 2220' w/200 sx, 3050' w/400 & 1500' w/120 sx cement

2nd plug perforate at 1200' and pull tubing to 1200' and circulate cement

3rd plug pull tubing and pump down 4 1/2" with 80 sx cement,

4th plug pump 10 sx cement down 8 5/8" X 4 1/2" annulus.

RECEIVED STATE CORPORATION COMMISSION FEB 24 1994 2-24-94 CONSERVATION DIVISION WICHITA, KANSAS Richard W. Lacey (TECHNICIAN)

Plugging Proposal Received by

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2 p.m. Day: 21 Month: 2 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug ran tubing to 4508' and pumped 23 sx gel and 25 sx cement with 100 lbs. hulls,

2nd plug perforated at 1200', pulled tubing to 1200' and circulated cement to surface,

3rd plug pulled tubing and pumped down 4 1/2" with 80 sx cement. Shut in pressure 400 psi.

4th plug pumped 10 sx cement down 8 5/8" X 4 1/2" annulus. Maximum pressure 500 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery. (additional description is necessary, use BACK of this form.)

INVOICED

DATE FEB 25 1994 (old / XXXXXXX) observe this plugging.

Signed Richard W. Lacey (TECHNICIAN)

WV. NO. 40041