

To: 1 090696
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 135-23,938-6000
SW NW SE, SEC. 13, T 16 S, R 26 W/E
1650 feet from S section line
2310 feet from E section line

6-16
TECHNICIAN'S PLUGGING REPORT
Operator License # 4689
Operator: Thomas C. Lutz
Name:
Address P.O. Drawer 3067
Lawrence, KS 66046

Lease Name Evel "P" A Well # 4
County Ness 148.52
Well Total Depth 4570 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 343

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWO Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Discovery Drilling, Inc. License Number 31548
Address P.O. Box 763, Hays, KS 67601

Company to plug at: Hour: 2:30 a.m. Day: 16 Month: 6 Year: 19 96

Plugging proposal received from Tom Alm
(company name) Discovery Drilling, Inc. (phone) 913-623-2920

was: to fill hole with heavy mud and spot cement through drill pipe Anhydrite Base 1995'
1st plug at 1995' with 50 sx cement, 2nd plug at 1150' with 80 sx cement,
3rd plug at 650' with 40 sx cement, 4th plug at 370' with 50 sx cement,
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,
7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5 a.m. Day: 16 Month: 6 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug at 1995' with 50 sx cement,
2nd plug at 1150' with 80 sx cement,
3rd plug at 650' with 40 sx cement,
4th plug at 370' with 50 sx cement, 5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement,
7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE JUN 24 1996

INV. NO. 45848

Signed _____ (TECHNICIAN)

6-16 AUG 21 1996

EFFECTIVE DATE: 6-4-96
DISTRICT # 1
SCA7...Yes.../No

State of Kansas 135-23,938-0000
NOTICE OF INTENTION TO DRILL

FORM MUST BE TYPED
FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well.

Expected Spud Date 6 8 1996
month day year

Spot SW NW SE Sec 13 Twp 16 S, Rg 26 East X West

OPERATOR: License # 4689
Name: Thomas C. Lutz
Address: P.O. Drawer 3067
City/State/Zip: Lawrence, Kansas 66046
Contact Person: Thomas C. Lutz
Phone: (913) 832-1119

1650 feet from South West line of Section
2310 feet from East West line of Section
IS SECTION X REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)

CONTRACTOR: License #: 31548
Name: Discovery Drilling, Inc.

County: Ness
Lease Name: Evel "B" Well #: 4
Field Name: Arnold SW

Is this a Prorated/Spaced Field? yes X, no ✓
Target Formation(s): Mississippian
Nearest lease or unit boundary: 1650'

Well Drilled For: Well Class: Type Equipment:
X Oil ... Enh Rec X Infield X Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OAWO ... Disposal ... Wildcat ... Cable
... Seismic; ... # of Holes ... Other
... Other

Ground Surface Elevation: 2570 Est feet MSL
Water well within one-quarter mile: yes X, no ✓
Public water supply well within one mile: yes X, no ✓

If ~~OWO~~ old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Depth to bottom of fresh water: 240'
Depth to bottom of usable water: 1150'
Surface Pipe by Alternate: 1 X, 2 ✓

Length of Surface Pipe Planned to be set: 340'
Length of Conductor pipe required: None
Projected Total Depth: 4600'

Formation at Total Depth: Mississippian
Water Source for Drilling Operations:
... well X, farm pond other

Directional, Deviated or Horizontal wellbore? yes X, no
If yes, true vertical depth:
Bottom Hole Location:

Will Cores Be Taken?: yes X, no
If yes, proposed zone:
260' Alt. II Req.

Exp. 11/30/96

AFFIDAVIT

RECEIVED

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with the provisions of the Act, et. seq.
It is agreed that the following minimum requirements will be met:

6-8-96

Pusher Tom

SPUD DATE 6-8-96 INIT. BLW

LENGTH SURFACE PLANNED 340'

RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 1/2" @ 393 CONDUCTOR
ANHYDRITE T. B-1441 ELEVATION

TP 4570 FORMATION

MAN PIPE @ SX DV TOOL ALT II DONE
SX Y N

Arbuckle Plug @ FT. W/ SX

Plug/Council @ FT. W/ SX

Anhydrite Base @ 1445 FT. W/ SX

1/2 Base Anyh. @ 1445 FT. W/ SX

1/2, 1/2 Plug @ 1445 FT. W/ SX

Bottom Surface @ 1445 FT. W/ SX

40' Plug @ 1445 FT. W/ SX

NAT HOLE CIRC/W SX MOUSE HOLE W/ SX

WATER WELL SX (Irr. Well Fond)
Hauling

TECHNICIAN DATE 02-11-96 02-11-96

TYPE OF CEMENT 100% SWS(NV)

STARTING TIME 2:00 (AM/PM) DATE 6/8/96

COMPLETION TIME 1:00 (AM/PM) DATE 6/8/96

EMENT COMPANY Discovery Drilling, Inc.