

To: 1 031390  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 135-23,923. ~~6870~~

NE SW NE, SEC. 11, T 16 S, R 26 W/E

1650 feet from NS section line

1650 feet from E section line

3-26

TECHNICIAN'S PLUGGING REPORT

Operator License # 31552

Lease Name Peterson Well # 2

Operator: Dennis Kindsvater

County Ness

Name & Address P.O. Box 906

Well Total Depth 4551 147.90 feet

Dodge City, KS 67801

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 360.73

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Discovery Drilling, Inc. License Number 31548

Address P.O. Box 763, Hays, KS 67601

Company to plug at: Hour: 5 a.m. Day: 26 Month: 3 Year: 19 96

Plugging proposal received from Tom Alm

(company name) Discovery Drilling, Inc. (phone) 913-623-2920

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2023-57'

1st plug at 2040' with 50 sx cement, 2nd plug at 1260' with 80 sx cement,

3rd plug at 690' with 40 sx cement, 4th plug at 360' with 40 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 8 a.m. Day: 26 Month: 3 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug at 2040' with 50 sx cement,

2nd plug at 1260' with 80 sx cement, 3rd plug at 690' with 40 sx cement,

4th plug at 360' with 40 sx cement,

5th plug at 40-0' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED

Conserve this plugging.

DATE MAR 28 1996

INV. NO. 45149

Signed Steve Durrant (TECHNICIAN)

3-26 JUN 27 1996 JUL 17 1996

RECEIVED STATE CORPORATION COMMISSION CONSERVATION DIVISION MAR 27 1996

