

10-3

To: 1 051209
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-23,383-0000
SE SW SE, SEC. 11, T 16 S, R 26 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 4689
Operator: Thomas C. Lutz
Name & Address: P.O. Drawer 0940
Fayetteville, AR 72702

330 feet from S section line
1650 feet from E section line
Lease Name Dorsa Well # 1
County Ness 149.50
Well Total Depth 4600 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 367

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Red Tiger Drilling Company License Number 5302

Address 1720 Kansas State Bank & Trust Building, Wichita, KS 67202

Company to plug at: Hour: 11 a.m. Day: 3 Month: 10 Year: 19 89

Plugging proposal received from Mike Waggoner

(company name) Red Tiger Drilling Company (phone) 316-263-2371

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1994-2029'
1st plug at 2010' with 50 sx cement, 2nd plug at 990' with 80 sx cement,
3rd plug at 390' with 40 sx cement, 4th plug at 40-0' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 3 p.m. Day: 3 Month: 10 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 2010' with 50 sx cement,
2nd plug at 990' with 80 sx cement,
3rd plug at 390' with 40 sx cement,
4th plug at 40-0' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

RECEIVED
STATE CORPORATION COMMISSION
10-5-89
OCT 05 1989

(If additional description is necessary, use BACK of this form.)

observe this plugging.

DATE 10-11-89

Signed Richard M. Lacy (TECHNICIAN)

INV. NO. 26086
10-3

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date Sept 30 1989 month day year

SE SW SE/4 Sec 11 Twp 16 S, Rg 26 X East West

OPERATOR: License # 4689 Name: Thomas C. Lutz Address: P.O. Drawer 0940 City/State/Zip: Fayetteville, Ark 72702 Contact Person: H. L. Maddox Phone: 316-653-4178

330 feet from South line of Section 1650 feet from East line of Section (Note: Locate well on Section Plat Below)

CONTRACTOR: License # 5302 Name: Red Tiger Drilling

County: NESS Lease Name: DOKSA Well #: 1 Field Name: UNKNOWN

Well Drilled For: Well Class: Type Equipment: XX Oil Inj Infield XX Mud Rotary Gas Storage Pool Ext Air Rotary OAWO Disposal X Wildcat Cable Seismic # of Holes

Is this a Prorated Field? yes X no Target Formation(s): MISSISSIPPI Nearest lease or unit boundary: 330 Ground Surface Elevation: NA Feet MSL Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no Depth to bottom of fresh water: 1500 180 Depth to bottom of usable water: 960 Surface Pipe by Alternate: 1 X 2 Length of Surface Pipe Planned to be set: 350 Length of Conductor pipe required: None Projected Total Depth: 4650 Formation at Total Depth: 4600 Water Source for Drilling Operations: Law well X farm pond other

If OAWO: old well information as follows: Operator: Well Name: Comp. Date: Old Total Depth


Directional, Deviated or Horizontal wellbore? yes X no If yes, total depth location: 3/8/90 Spud 9-26-89

DWR Permit #: Will Cores Be Taken?: yes X no If yes, proposed zone: 200' Alt. II Req.

AFFIDAVIT

PUSHER Mike Kinger TD 4600 FORMATION MISS SURFACE PIPE 8 7/8 @ 367 ANHYDRITE 1994 ELEVATION 2029 STARTING TIME & DATE 11:00 AM - 10-3-89 COMPLETION TIME & DATE 3:00 pm 10-3-89 1st PLUG @ 2010 FT. W/ 50 SX 2nd PLUG @ 990 FT. W/ 80 SX 3rd PLUG @ 390 FT. W/ 40 SX 4th PLUG @ 40-0 FT. W/ 10 SX RAT HOLE CIRCULATED W/ 15 SX MOUSE HOLE CIRCULATED W/ SX WATER WELL PLUGGED W/ Slurried CEMENT COMPANY 60/40 for 670 TECHNICIAN S.D. Lacey sawall TYPE OF CEMENT Cellulose

UTICA 1/4 E 2 N -



Spud date: OCT 05 1989 Agent: [Signature]

- REMEMBER TO: - File Drill Pit Application (form CDP-1) with Intent to Drill; - File Completion Form ACO-1 within 120 days of spud date; - File acreage attribution plat according to field proration orders; - Notify appropriate district office 48 hours prior to workover or re-entry; - Submit plugging report (CP-4) after plugging is completed; - Obtain written approval before disposing or injecting salt water.