

1 120013

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- - 135-21,739-0000  
C W/2 W/2  
NW, SEC. 11, T 16 S, R 26 W/EX  
3960 FEET FROM N/S SECTION LINE  
4950 FEET FROM W/E SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 5144

LEASE NAME Snyder WELL # 3

OPERATOR: Mull Drilling Company, Inc.  
NAME & ADDRESS: P.O. Box 2758  
Wichita, KS 67201

COUNTY Ness

WELL TOTAL DEPTH 4557 FEET <sup>148.11</sup>

CONDUCTOR PIPE: SIZE \_\_\_\_\_ FEET

SURFACE CASING: SIZE 8 5/8 FEET 252

ABANDONED OIL WELL x GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD WELL \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR Mull Drilling Co., Inc. LICENSE NUMBER 5144

ADDRESS P. O. Box 2758, Wichita, KS 67201

COMPANY TO PLUG AT: HOUR: 3:00 pm DAY: 13 MONTH: May YEAR: 19 85

PLUGGING PROPOSAL RECIEVED FROM Jerry Roane

(COMPANY NAME) Mull Drilling Company, Inc. (PHONE) 316-264-6366

WERE: 4 1/2" at 4552' Open Hole from 4552-57' Dakota Base is at 1025'

1st plug sand back to 4500' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 10 sx gel, 70 sx cement, 10 sx gel, and 175

sx cement, 1 sack hulls, 10 sx gel and 250 sx cement.

PLUGGING PROPOSAL RECEIVED BY Steve Durrant  
(TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL x PART \_\_\_\_\_ NONE \_\_\_\_\_

OPERATIONS COMPLETED: HOUR: 4:30 pm DAY: 13 MONTH: May YEAR: 19 85

ACTUAL PLUGGING REPORT Tubing stuck - pulled off at 895'. Unable to clean out hole.

720' 4 1/2" casing recovered. Perforated with 4 shots at 895' - spotted 50 sx cement

through tubing at 890'. Hooked onto 8 5/8" surface casing and pumped down 14 bbls of

mud with 25# flowseal and 125 sx cement.

Maximum pressure 150 psi and shut in 100 psi

RECEIVED  
STATE CORPORATION COMMISSION  
5-21-85  
MAY 21 1985

CONSERVATION DIVISION  
Wichita, Kansas

REMARKS: Used 50/50 Pozmix 6% gel by Halliburton. 5-16-85 - tagged cement in 8 5/8"

casing at 8 feet below ground surface.

I (DID / ~~DOES NOT~~) OBSERVE THIS PLUGGING.

SIGNED Don C. Uebel  
(TECHNICIAN)

FORM CP-2/3  
REV. 6-83

INDEXED  
DATE 5-21-85  
INV. NO. 8215  
5-13