

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-23670-00-00
Spot: NESWNW Sec/Twnshp/Rge: 18-32S-5E
3640 feet from S Section Line, 4244 feet from E Section Line
Lease Name: LUMBERT Well #: 7
County: COWLEY Total Vertical Depth: 2479 feet

Operator License No.: 33277
Op Name: COOPER, ALBERT L. DBA COOPER SER
Address: PO BOX 381
WINFIELD, KS 67156

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2478	156	150 SX
SURF	8.625	256		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/29/2013 8:00 AM
Plug Co. License No.: 33277 Plug Co. Name: COOPER, ALBERT L. DBA COOPER SERVICE CO.
Proposal Revd. from: ALBERT COOPER Company: COOPER SERVICE CO Phone: (316) 204-0072

Proposed Plugging Method: AS PER KCC RULES & REGS /SAND @ 2350, W/4 SXS. 310-0 CIRC. CEMENT

Plugging Proposal Received By: DAN FOX Witness Type: PARTIAL
Date/Time Plugging Completed: 08/15/2013 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG CIRCULATING VARIOUS BRIDGES @ 2360'. CIRCULATED HOLE CLEAN. 8-6-2013, SANDED WELL BACK @ 2310', DUMP BAILED 4 SXS CEMENT ON TOP. TAGGED PLUG @ 2290'. 8-7-2013, CUT CASING @ 156', LAYED DOWN 4 JOINTS 4 1/2" CASING (156'). 8-15-2013, RIH W/TBG @ 300', COOPER SERVICE ESTABLISHED CIRCULATION, PUMPED 80 SXS 60/40 POZMIX TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM 8-15-2013. DANIELS READY MIX CEMENT TICKET #028835.

Perfs:

Top	Bot	Thru	Comments
2434	2438	CSG	
2414	2438		

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: COMPLIANCE/ 10 YEAR RULE / DENIED TA

AUG 22 2013

Plugged through: TBG

CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed

DUANE KRUEGER
9/06/13 (TECHNICIAN)