

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-21874-00-00
Spot: SWSESESW Sec/Twnshp/Rge: 3-32S-7E
258 feet from S Section Line, 2997 feet from E Section Line
Lease Name: BARGER Well #: 17
County: COWLEY Total Vertical Depth: 2485 feet

Operator License No.: 33711
Op Name: B-C STEEL, LLC
Address: 209 N FRY ST
YATES CENTER, KS 66783

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2485		150 SX
SURF	8.625	150		75 SX
SURF		200		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/15/2013 8:00 AM
Plug Co. License No.: 31074 Plug Co. Name: BRAKE, JOE DBA BRAKE INC.
Proposal Revd. from: RON WHITEMAN Company: GENDOR OIL CO. Phone: (620) 467-2615

Proposed
Plugging
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 07/16/2013 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

TAGGED TD @ 2150'. SANDED WELL BACK @ 2100', DUMP BAILED 4.5 SACKS CEMENT ON TOP. TAGGED BTM PLUG @ 2090'. 7-16-2013, RIH ON WIRELINE CUT CASING @ 374', COULD NOT PULL CASING. RIH W.1" TBG ON BACKSIDE @ 270', BRAKE OIL, PUMPED 95 SXS 60/40 POZMIX TO SURFACE. LAYED DOWN 1" TBG. RIH W/TBG @ 350', BRAKE OIL PUMPED 45 SXS 60/40 POZMIX TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM 7-16-2013. DANIELS READY MIX TICKET #028686.

Remarks: COMPLIANCE / 10 YEAR RULE

Plugged through: TBG

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 23 2013

CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed

Duane Krueger
8/27/13
(TECHNICIAN)