

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-20541-00-00  
Spot: NESENWSE Sec/Twnshp/Rge: 3-32S-7E  
1876 feet from S Section Line, 1359 feet from E Section Line  
Lease Name: BARGER B Well #: 1  
County: COWLEY Total Vertical Depth: 2855 feet

Operator License No.: 33711  
Op Name: B-C STEEL, LLC  
Address: 209 N FRY ST  
YATES CENTER, KS 66783

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2212		100 SXS
PROD	4.5	2855	365	100 SXS CMT
SURF	10.375	210		200 SXS CMT
SURF	8.65	350		75 SXS

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/11/2013 8:00 AM  
Plug Co. License No.: 31074 Plug Co. Name: BRAKE, JOE DBA BRAKE INC.  
Proposal Rcvd. from: RON WHITEMAN Company: GENDOR OIL CO Phone: (620) 467-2615

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 07/17/2013 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

TAGGED TD @ 2855'. SANDED WELL BACK @ 2780', DUMP BAILED 5 SXS CEMENT ON TOP. TAGGED BOTTOM PLUG @ 2746'. 7-16-2013, RIH ON WIRELINE CUT CASING @ 365', LAYED DOWN 10 JOINTS CASING. 7-17-2013, RIH W/TBG @ 350', BRAKE OIL PUMPED 140 SXS 60/40 POZMIX TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM 7-17-2013. DANIELS READY MIX TICKET #028692.

Perfs:

Top	Bot	Thru	Comments
2830	2840	CSG	

RECEIVED  
KANSAS CORPORATION COMMISSION

**AUG 23 2013**

CONSERVATION DIVISION  
WICHITA, KS

Remarks: COMPLIANCE / 10 YEAR RULE/ TD ON WELL @ 2855'

Plugged through: TBG

District: 02

Signed

Duane Krueger  
8/23/13  
(TECHNICIAN)