

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-19523-00-00
Spot: SWNENENW Sec/Twnshp/Rge: 31-31S-6E
4924 feet from S Section Line, 2982 feet from E Section Line
Lease Name: MCMINN Well #: 1
County: COWLEY Total Vertical Depth: 2962 feet

Operator License No.: 33711
Op Name: B-C STEEL, LLC
Address: 209 N FRY ST
YATES CENTER, KS 66783

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5	2946		
PROD	4.5	2962		150 SX
SURF	8	119		
SURF	8.625	150		75 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/06/2013 8:00 AM
Plug Co. License No.: 31074 Plug Co. Name: BRAKE, JOE DBA BRAKE INC.
Proposal Rcvd. from: BRENT WHITEMAN Company: GENDOR OIL CO Phone: (620) 467-2615

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: _____ Witness Type: PARTIAL
Date/Time Plugging Completed: 06/13/2013 12:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED WELL BACK @2000', DUMP BAILED 5 SX CEMENT ON TOP OF SAND. RIH W/1" TBG ON BACKSIDE OF CASING @ 200', BRAKE OIL ESTABLISHED CIRCULATION, & PUMPED 35 SXS 60/40 POZMIX TO SURFACE. LAYED DOWN 1" TBG. RIH W/TBG @ 400', BRAKE OIL ESTABLISHED CIRCULATION, & PUMPED 85 SXS 60/40 POZMIX TO SURFACE. CEMENT CIRCULATED. LAYED DOWN TBG, TOPPED WELL BACK TO SURFACE W/CEMENT. DANIELS READY MIX TICKET #028438.

Perfs:

Top	Bot	Thru	Comments
2100	2112	CSG	

Remarks: COMPLIANCE/ 10 YEAR RULE

Plugged through: TBG

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 22 2013

CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed

Duane Krueger
8/23/13 (TECHNICIAN)

✓JK