

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-20840-00-00
Spot: SWNWSWSE Sec/Twnshp/Rge: 3-32S-7E
969 feet from S Section Line, 2351 feet from E Section Line
Lease Name: BARGER Well #: 14
County: COWLEY Total Vertical Depth: 2225 feet

Operator License No.: 33711
Op Name: B-C STEEL, LLC
Address: 209 N FRY ST
YATES CENTER, KS 66783

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| CIBP | | 1900 | | |
| PROD | 4.5 | 2224 | | 102 SX |
| SURF | 8.625 | 197 | | 75 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/14/2013 8:00 AM
Plug Co. License No.: 31074 Plug Co. Name: BRAKE, JOE DBA BRAKE INC.
Proposal Rcvd. from: RON WHITEMAN Company: GENDOR OIL CO Phone: (620) 467-2615

Proposed
Plugging
Method:

AS PER KCC RULES & REGS /SAND @ 1790', W/4 SXS. CUT CSG 350'-0' CIRC. CEMENT.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 07/02/2013 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED WELL BACK @ 1790', DUMP BAILED 4 SXS CEMENT ON TOP. CUT CASING @ 360', LAYED DOWN 4-1/2" CASING. RIH W/TBG @360', GENDOR PUMPED 120 SXS 60/40 POZMIX TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM 7-2-2013. DANIELS READYMIX TICKET #028580.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 2140 | 2158 | | CSG |
| 1842 | 1852 | | CSG |

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: COMPLIANCE/ 10 YR RULE

AUG 22 2013

Plugged through: TBG

CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed Duane Krueger
8/29/13 (TECHNICIAN)

✓