

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21490-00-00
Spot: NESWNSE Sec/Twnshp/Rge: 16-28S-8W
1922 feet from S Section Line, 1983 feet from E Section Line
Lease Name: MCKENNA Well #: 16-1
County: KINGMAN Total Vertical Depth: 4465 feet

Operator License No.: 4706
Op Name: MESSENGER PETROLEUM, INC.
Address: 525 S MAIN ST
KINGMAN, KS 67068

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4290		
PROD	5.5	4464		200 SX
SURF	8.625	209		150 SX

Well Type: SWD UIC Docket No: D27292.0 Date/Time to Plug: 04/20/2013 12:00 AM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Revd. from: RICHARD MCINTYRE Company: Phone: (620) 532-5400

Proposed Plugging Method: sand over Miss perf's to 3950, 35sx cement plug @ 1300', 35 sx cement plug @ 750', 35sx cement plug @ 200', cement from 80' to surface: OR as per KCC recommendations.

Plugging Proposal Received By: STEVE VANGIESON

WitnessType: PARTIAL

Date/Time Plugging Completed: 08/06/2013 4:00 PM

KCC Agent: B. J. HOPE

Actual Plugging Report:

PUMPED 25 SX CEMENT AND 200 LBS OF HULLS, ON 8-5-13. 8/6/13 --TAGGED TOP OF CEMENT @ 3300'. CUT CASING PIPE OFF @ 3030' PULLED CASING TO 1200' SPOTTED 35 SX CEMENT. PULLED CASING TO 750' SPOTTED 35 SX CEMENT. PULLED CASING TO 250' CIRCULATED TO SURFACE WITH 110 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
4370	4374		
4330	4340		
4006	4010		
3994			

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 13 2013

CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY WELL SERVICE PROVIDED CEMENTING EQUIPMENT AND CEMENT ALSO. COMMISSION ORDER FAILURE TO TEST AND TA.

Plugged through: CSG

District: 02

Signed

B. J. Hope

(TECHNICIAN)