

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-05957-00-00  
Spot: NWNESE Sec/Twnshp/Rge: 33-14S-13W  
2310 feet from S Section Line, 990 feet from E Section Line  
Lease Name: HENRY MICHEL Well #: 2  
County: RUSSELL Total Vertical Depth: 2850 feet

Operator License No.: 3134

String Size Depth (ft) Pulled (ft) Comments

Op Name: MORRIS, TERRY E. DBA G L M COMPANIES

PROD 5.5 2850

Address: PO BOX 193

SURF 7 2355

RUSSELL, KS 67665

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 07/30/2013 8:30 AM

Plug Co. License No.: 34071

Plug Co. Name: PATRIOT WELL SERVICE, INC.

Proposal Rcvd. from: DAN

Company: GLM COMPANY

Phone: (785) 483-1307

Proposed  
Plugging  
Method:

Ordered 300 sx 60/40 pozmix 4% gel cement, 150 sx class A w/3% C.C. and 2% gel and 500 # hulls.  
Perforations: 1500', 630' and 200'.  
Drilled out CIB plug and found junk in the bottom. 7" pipe was the only pipe remaining. Everything else had been pulled.

Plugging Proposal Received By: CASE MORRIS

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 07/30/2013 3:00 PM

KCC Agent: RAY DINKEL

*Ray Dinkel*  
8/19/13

Actual Plugging Report:

Perfs:

Ran tubing to 2835' and pumped 150 sx cement w/200 # hulls in the last of cement.  
Pulled tubing to 1350' and pumped 130 sx cement w/100 # hulls.  
Circulated cement out back side. Shut in. Circulated cement out braden head.  
Pumped 80 sx cement and lost circulation.  
POOH. Hooked to casing and pumped 50 sx cement. Circulated cement out braden head. Shut in and pumped 20 sx cement at 300 psi. Shut in.

GPS: 38.79032 -098.76588

Remarks: QUALITY CEMENTING TICKET # 7275

Plugged through: TBG

District: 04

Signed

*Ray Dinkel*  
8/22/13

(TECHNICIAN)

CM

RECEIVED  
KANSAS CORPORATION COMMISSION

Form CP-2/3

AUG 05 2013

AUG 09 2013

CONSERVATION DIVISION  
WICHITA, KS