

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-23228-00-00
Spot: S2SWNW Sec/Twnshp/Rge: 18-32S-5E
2977 feet from S Section Line, 4545 feet from E Section Line
Lease Name: LUMBERT Well #: 4
County: COWLEY Total Vertical Depth: 2505 feet

Operator License No.: 33277
Op Name: COOPER, ALBERT L. DBA COOPER SER
Address: PO BOX 381
WINFIELD, KS 67156

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1825		
PROD	5.5	2496		200 SX
SURF	8.625	200		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/09/2013 8:00 AM
Plug Co. License No.: 33277 Plug Co. Name: COOPER, ALBERT L. DBA COOPER SERVICE CO.
Proposal Rcvd. from: ALBERT COOPER Company: COOPER SERVICE CO Phone: (316) 204-0072

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 05/23/2013 12:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG CIRCULATING VARIOUS BRIDGES @ 1751', CIRCULATED HOLE CLEAN. RIH W/TBG @ 1750', COOPER SERVICE CO. ESTABLISHED CIRCULATION, PUMPED 25 SXS 60/40 POZMIX & DISPLACED IN CASING. POOH W/TBG @ 960', COOPER SERVICE PUMPED 30 SXS 60/40 POZMIX & DISPLACED IN CASING, RIH W/TBG @ 300', COOPER SERVICE ESTABLISHED CIRCULATION, PUMPED 160 SXS 60/40 POZMIX TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 12:00 PM - 5-23-2013. DANIELS READY MIX CEMENT TICKET # 028328, & 028320.

Perfs:

Top	Bot	Thru	Comments
1985	1990	CSG	

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 16 2013
CONSERVATION DIVISION
WICHITA, KS

Remarks: NO CASING IN WELL. PRODUCTION CASING WAS PULLED ON THIS WELL @ EARLIER DATE @ APPROX. 955', COMPLIANCE/ 10 YEAR RULE / DENIED TA

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER
8/20/13 (TECHNICIAN)

JK