

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-23548-00-00  
Spot: W2SWNW Sec/Twnshp/Rge: 18-32S-5E  
3628 feet from S Section Line, 4864 feet from E Section Line  
Lease Name: LUMBERT Well #: 6  
County: COWLEY Total Vertical Depth: 2474 feet

Operator License No.: 33277  
Op Name: COOPER, ALBERT L. DBA COOPER SER  
Address: PO BOX 381  
WINFIELD, KS 67156

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2470	900	150 SX
SURF	8.625	255		200 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/06/2013 8:00 AM  
Plug Co. License No.: 33277 Plug Co. Name: COOPER, ALBERT L. DBA COOPER SERVICE CO.  
Proposal Rcvd. from: ALBERT COOPER Company: COOPER SERVICE CO. Phone: (316) 204-0072

Proposed Plugging Method: AS PER KCC RULES & REGS / SAND @ 2200 W/5 SXS, 310' - 0' CIRC CEMENT/ 30 SXS ON BOTTOM, 20 SXS @ 900', CIRCULATE 305'-0'.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL  
Date/Time Plugging Completed: 06/19/2013 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG CIRCULATING VARIOUS BRIDGES @ 2150'. CIRCULATED HOLE CLEAN. RIH W/TBG @ 2150', COOPER SERVICE CO. ESTABLISHED CIRCULATION, PUMPED 30 SXS 60/40 POZMIX & DISPLACED IN CASING. POOH W/TBG @ 960', COOPER SERVICE PUMPED 20 SXS 60/40 POZMIX & DISPLACED IN CASING. RIH W/TBG @ 310', COOPER SERVICE ESTABLISHED CIRCULATION, PUMPED 140 SXS 60/40 POZMIX TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM 6-19-2013. DANIELS READY MIX CEMENT TICKET # 028480.

Perfs:

Top	Bot	Thru	Comments
1985	1990	CSG	

RECEIVED  
KANSAS CORPORATION COMMISSION

**AUG 16 2013**

CONSERVATION DIVISION  
WICHITA, KS

Remarks: NO CASING IN WELL, PRODUCTION CASING WAS PULLED ON THIS WELL @ EARLIER DATE @ APPROX 960', COMPLIANCE /10 YEAR RULE/DENIED TA

Plugged through: TBG

District: 02

Signed

*Duane Krueger*  
8/20/13  
(TECHNICIAN)