

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 135-23922 0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Scott T. Lutz / Scott T. Lutz KCC LICENSE # 7200
(owner/company name) (operator's)

ADDRESS P.O. Drawer D CITY Shell Knob

STATE MO ZIP CODE 65747 CONTACT PHONE # (501) 443-5430

LEASE Evel "B" WELL# 3 SEC. 13 T. 16S R. 26 (EMX/West)

100'W - E/2 - E/2 - SE SPOT LOCATION/0000 COUNTY Ness

1320 FEET (in exact footage) FROM (S)/N (circle one) LINE OF SECTION (NOT Lease Line)

430 FEET (in exact footage) FROM (E)/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8 SET AT 358.14 CEMENTED WITH 210 SACKS

PRODUCTION CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: _____

ELEVATION 2542/ 2550 T.D. 4503 PBDT _____ ANHYDRITE DEPTH (1945-1977)
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING (1st Plug @ 1980' w/50sks)(2nd Plug @ 1250' w/80sks)

(3rd Plug @ 390' w/50sks)(4th Plug @ 40' w/10sks)(10sks In Mouse Hole)(15sks In Rat Hol.

215sks Total 60/40Poz 6%Gel w/1/4#FS/sk By Haliburton Completed @ 6:15 AM 3/19/96

(if additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No Log IS ACO-1 FILED? Yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Thomas H. Alm PHONE# (913) 625-5183

ADDRESS 1922 Whittier City/State Hays, Kansas 67601

PLUGGING CONTRACTOR Discovery Drilling, Inc. KCC LICENSE # 31548

ADDRESS P.O. Box 763 Hays, Kansas 67601 (contractor's name) (contractor's)

PHONE # (913) 623-2920

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 3/19/96 6:15 AM

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 4/15/96 AUTHORIZED OPERATOR/AGENT: _____

(signature)

APR 12 1996

4-18-96