

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 135-23939 0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Scott T. Lutz / Scott T. Lutz KCC LICENSE # 7200
(owner/company name) (operator's)

ADDRESS P.O. Drawer D CITY Shell Knob

STATE MO ZIP CODE 65747 CONTACT PHONE # (501) 443-5430

LEASE Nies WELL# 1 SEC. 12 T. 16s R. 26 (~~East~~/West)

SE - SW - NW SPOT LOCATION/QQQQ COUNTY Ness

2310 FEET (in exact footage) FROM S/(N) (circle one) LINE OF SECTION (NOT Lease Line)

990 FEET (in exact footage) FROM E/(W) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8 SET AT 271.49 CEMENTED WITH 170 SACKS

PRODUCTION CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: _____

ELEVATION 2588/2596 T.D. 4547 PBTD _____ ANHYDRITE DEPTH (2002-2039)
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING (1st Plug @ 2040' w/50sks)(2nd Plug @ 1250' w/80sks)

(3rd Plug @ 300' w/40sks)(4th Plug @ 40' w/10sks)(10sks In Mouse Hole)(15sks In Rat Hole)

Total 205sks 60/40Poz 6%Gel w/1#FS/sk By Allied Cementing Completed @ 9:15AM 7/16/96
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No Log IS ACO-1 FILED? Yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Thomas H. Alm PHONE# (918) 625-5183

ADDRESS 1922 Whittier City/State Hays, Kansas 67601

PLUGGING CONTRACTOR Discovery Drilling, Inc. KCC LICENSE # 31548

ADDRESS P.O. Box 763 Hays, Kansas 67601 PHONE # (918) 623-2920
(Company name) (contractor's)

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 7/16/96 @ 9:15 AM

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 8-7-96 AUTHORIZED OPERATOR/AGENT: Scott T. Lutz

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 05 1996
8-5-96
CONSERVATION DIVISION
WICHITA, KS