

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION

NOV 14 1973  
11-14-73  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Donald C. Slawson

Complete Address 408 One Twenty Bldg., Wichita, Kansas

Lease Name Thornburg "D" Well No. 1

Location SW SE NW Sec. 3 Twp. 16 Rge. (E) (W) 26

County Ness Total Depth 4077'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor        Co. Tools       

Address        License No.       

Operation Completed: Hour 3 P Day 10 Month 11 Year 1973

The above well was plugged as follows:

RTD 4077' 8 5/8 csg set at 297' cwc 200 sk. Cmt. Mat. 50-50 poz W6% total gel.  
Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sk  
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo. Z. [Signature]  
Well Plugging Supervisor

DATE 11/14/73

INV. NO. 8168-10