

15-135-21627-0800

Form CP-3

Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

APR 1 1975  
4-1-75  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Donald C. Slawson

Complete Address 408 120 Bldg., Wichita, Kansas

Lease Name Nelson "R" Well No. 1

Location NW NE SE Sec. 3 Twp. 16 Rge. (E) (W) 26

County Ness Total Depth 4590'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Co. Tools

Address        License No.       

Operation Completed: Hour 10:45 A Day 28 Month 3 Year 1975

The above well was plugged as follows:

RTD 4590' 8 5/8 csg set 288' cwc 160 sk. Flg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 800' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar,

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/9/75  
INV. NO. 1135-W

Signed: Les F. Massey  
Well Plugging Supervisor