



Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
MAR 24 1975
3-21-75
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Texas Oil & Gas Corp

Complete Address Suite 450 200 W Douglas Wichita, KS

Lease Name Stone Well No. 1

Location C NE/SE Sec. 10 Twp. 32 Rge. 11 (E) (W)W

County Barber Total Depth 4530

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Clarke Oilfield Service

Address Box 187 Medicine Lodge, KS License No. 583

Operation Completed: Hour 10:00 AM Day 20 Month 3 Year 1975

The above well was plugged as follows:

371 ft 8 5/8 surface cemented with 300 sacks. 4529 ft 4 1/2 long string
cemented with 125 sacks. Top perf. 4310 ft. Sand to 4290 ft, 4
sacks cement with bailer. Pulled 3820 ft 4 1/2. Set 10 ft rock bridge
at 240 ft. Fill hole with 4 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 3/26/75

INV. NO. 1054-W